



Quote

From:

Full Force Heating & Cooling
459 Main Street
Suite 101, Box 379
Trussville, AL 35173
brandon@fullforcehvac.com

Quote Number	QUO-4
Quote Date	May 25, 2023
Total	\$0.00

To:

Kasey Summers
114 Victoria Ave
Trussville, AL 35173
kaseytsummers@gmail.com

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	American Standard 2 ton AC, Coil, 80% Gas Furnace 14 SEER 2 Will include new auxiliary drain pan. In line drain safety switch to prevent water damage. Redoing flu pipe to furnace to allow coil to be faced the correct way for easier maintenance. New 4ft gas whip for furnace. Outside will have a new pad for outdoor unit. New disconnect outside & new electric whip going to unit. Will also include installation of new wifi thermostat if customer chooses to get one from Vivint. \$9,620.00	\$0.00	0%	\$0.00



Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	American Standard 2 ton AC, Coil, 80% Gas Furnace 16 SEER 2 Stage Will include new auxiliary drain pan. In line drain safety switch to prevent water damage. Redoing flu pipe to furnace to allow coil to be faced the correct way for easier maintenance. New 4ft gas whip for furnace. Outside will have a new pad for outdoor unit. New disconnect outside & new electric whip going to unit. Will also include installation of new wifi thermostat if customer chooses to get one from Vivint. \$10,700.00	\$0.00	0%	\$0.00
1	Bryant 2 ton AC, Coil, 80% Gas Furnace 14 SEER 2 Will include new auxiliary drain pan. In line drain safety switch to prevent water damage. Redoing flu pipe to furnace to allow coil to be faced the correct way for easier maintenance. New 4ft gas whip for furnace. Outside will have a new pad for outdoor unit. New disconnect outside & new electric whip going to unit. Will also include installation of new wifi thermostat if customer chooses to get one from Vivint. \$8,935.00	\$0.00	0%	\$0.00
1	Bryant 2 ton AC, Coil, 80% Gas Furnace 16 SEER 2 Stage Will include new auxiliary drain pan. In line drain safety switch to prevent water damage. Redoing flu pipe to furnace to allow coil to be faced the correct way for easier maintenance. New 4ft gas whip for furnace. Outside will have a new pad for outdoor unit. New disconnect outside & new electric whip going to unit. Will also include installation of new wifi thermostat if customer chooses to get one from Vivint. \$10,250.00	\$0.00	0.00%	\$0.00



Quote

Sub Total	\$0.00
Tax	\$0.00
Total	\$0.00



Quote

These units will come with factory 10 year parts warranty, 1 year labor. Customer can purchase 10 year labor warranty through JB Warranties if desired for around \$1000, let me know if that is something you want to do.

This is a fixed price quote. If accepted, we require a 50% deposit upfront before work commences.
